



ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

201-MHz RF Cavity Construction (Plan) for MICE

Derun Li

**Center for Beam Physics
Lawrence Berkeley National Laboratory**

**NFMCC Meeting
March 17, 2008**




Outline

- **MICE Cavity Design**
 - **Based on the design of 201-MHz cavity for MUCOOL**
 - Cavity body
 - Ports for power coupler, vacuum and probes
 - RF power loop coupler and ceramic RF window
 - Curved Beryllium window
 - Tuners
 - Interface and integration with RFCC module
- **Summary**
 - **Status and fabrication plan**
 - Techniques developed for MUCOOL cavity
 - Spinning, port extruding, curved Be windows, RF couplers



ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

MICE Cooling Channel



MICE Cooling Channel
Courtesy of S. Q. Yang, Oxford Univ.



ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

MICE RF Cavity

- **Eight 201-MHz cavities + with materials for two more spares**
- **Baseline design: 201-MHz for MUCOOL, but**
 - **Cavity body profile needs to be modified**
 - Resonant frequency
 - Better estimation of spring back after spinning
 - **Port extruding**
 - Port interface is different from the MUCOOL cavity
 - **RF coupler and ceramic window**
 - Same as the MUCOOL cavity with Toshiba ceramic windows for SNS
 - **Curved Beryllium windows**
 - Modified design to better control silver alloy flow during the brazing
 - **Tuners and interface with RFCC module**
 - **Post-processing: Water cooling pipes, cleaning (EP & water rinsing), low power measurement, tuning, assembly and shipping**




Cavity Design Parameters

- **The cavity design parameters**
 - Frequency: 201.25 MHz
 - $\beta = 0.87$
 - Shunt impedance (VT^2/P): $\sim 22 \text{ M}\Omega/\text{m}$
 - Quality factor (Q_0): $\sim 53,500$
 - Be window radius and thickness: 21-cm and 0.38-mm
- **Nominal parameters for cooling channels in a muon collider or a neutrino factory and MICE**
 - $\sim 16 \text{ MV/m}$ ($\sim 8 \text{ MV/m}$) peak accelerating field
 - Peak input RF power $\sim 4.6 \text{ MW}$ ($\sim 1 \text{ MW}$) per cavity (85% of Q_0 , 3τ filling)
 - Average power dissipation per cavity $\sim 8.4 \text{ kW}$ ($\sim 1 \text{ kW}$ at 1 Hz repetition rate and 1 ms pulse length)
 - Average power dissipation per Be window
 $\sim 100 \text{ watts}$ ($\sim 12 \text{ watts}$)



MUCOOL Cavity Review



- Design and engineering at LBNL
- Half shells spun at Acme in Minnesota
- Parts made in Univ. of Mississippi and LBNL
- E-beam welding & port-pulling, cleaning and EP at J-Lab, NASA
- Coupler tests at SNS, Oak Ridge National Lab
- Final assembly and high power tests at MTA, FNAL (March-2006) and reached 16-MV/m without external magnetic field



ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

The Cavity Body Profile

Spherical section at the equator to ease addition of ports ($\pm \sim 6^\circ$)
Elliptical-like (two circles) nose to reduce peak surface field

2° tilt angle

6-mm Cu sheet permits spinning technique and mechanical tuners similar to SCRF ones


De-mountable **pre-curved Be windows** pointing in the same direction to terminate RF fields at the iris

Stiffener ring

Bolted Be window

E-beam joints

Low peak surface field and easy fabrication





ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

Cavity Body

- **MUCOOL cavity frequency is slightly lower than 200-MHz, but within the bandwidth of RF source**
 - Mechanical (fixed) tuners available and tested in air
- **MICE cavities**
 - Target frequency is 201.250-MHz
 - One RF source (tube) powers more than one cavity
 - Each cavity will be made (spinning) to frequency very close to 201-MHz
 - Modifying the existing mold used for MUCOOL cavity
 - A new mold (could be new materials)
 - 3D simulations to predict the frequency shifts by ports, curved Be windows and thermal contraction (LN operation)
 - Conceptual tuner designs (fine tuning)




ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

Ports Extruding and Flanges



Development of the technique



Cavity ports being extruded (pulled)



Extruded port



Port flange e-beam weld




Finished cavity port




ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

Fabrication of the Coupler




- The coupling can be adjusted by rotating the loop
- Water cooling line goes around the loop
- RF ceramic windows from Toshiba Company





RF Coupling Loop Design

- Prototype coupling loop design uses standard off-the-shelf copper co-ax
- Parts to be joined by torch brazing
- Coupling loop has integrated cooling
(Possible off-shelf components?)
- Two SNS style RF windows mfg. by Toshiba received (no cost!)
- Bellows connection required on MICE for thermal and dimensional reasons
- Need to integrate with MICE layout






ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

Curved Be Windows

- **We have made two windows available so far**
 - 21-cm and 0.38-mm thick
 - **Good** braze (between annular frames and foil)
 - Achieved ~ 95 % of the designed profile
 - Thin Ti-N coatings
- **The windows were HP tested at MTA, Fermilab**






ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

Beryllium Window Update

- Improved design for better brazing (based on suggestions from Brush-Wellman Company)






ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

Tuners for MICE Cavities

Four 201-MHz cavities in each RFCC module; one tuner assembly (six sets of tuners) on each cavity.




- Clocking of tuner position between adjacent cavities avoids interference
- Actuators offset from cavity center plane due to width of coupling coil
- Soft connection only (bellows) between tuner/actuators and vacuum vessel shell



ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

Tuner Section View





ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY


MUCOOL Cavity Tuners





Integration to RFCC Module

RF couplers, vacuum, RF probes, tuners, water cooling pipes







ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

Post-Processing

- Cavity cleaning and assembly
- Low power RF measurements and shipping





Summary

- **Status**

- Cavity design modifications have started
 - ✓ Cavity body profile and analysis (RF, thermal [watering cool + possible LN operation], mechanical, vacuum, ...)
 - ✓ Modified Be window designs, ready to place PO
 - Tuners and interface with RFCC module
- Apply successful techniques developed from MUCOOL cavity R&D and look for possible simplifications
 - Spinning, port extruding and post-processing
- Re-qualify vendors (spinning, e-beam welding, port extruding and post-processing) with our supervision
 - US vendors: NIOWAVE, ...
 - HIT in China
 - ✓ Brush-Wellman for Be windows
 - ✓ Toshiba for ceramic RF windows

- **Design and Fabrication Plan**

- Design review ~ June 2008 (MICE CM21 at DL)
- Schedule has been developed (~ by early 2010)

Microsoft Project - WBS-1.3.2-10-08-07(w_MC)

Type a question for help

File Edit View Insert Format Tools Project Collaborate Window Help Adobe PDF

No Group Show Arial 8 B I U

Tasks Resources Track Report

146,147,148,40,32

	WBS	Task Name	Duration	Start	Finish	Work	Original Fixed Cost [\$]	Predecessor
1	1	MICE	797.5 days	Mon 10/2/06	Wed 10/21/09	7,809.87 hrs	\$3,647,068	
2	1.1	MICE Integration	1 day	Mon 10/2/06	Mon 10/2/06	0 hrs	\$0	
3	1.2	Muon Beam Line & Infrastructure	1 day	Mon 10/2/06	Mon 10/2/06	0 hrs	\$0	
4	1.3	MICE Cooling Modules	797.5 days	Mon 10/2/06	Wed 10/21/09	7,809.87 hrs	\$3,647,068	
5	1.3.1	Absorber and Focus Coil Module	1 day	Mon 10/2/06	Mon 10/2/06	0 hrs	\$0	
6	1.3.2	Cavity and Coupling Coil Module	797.5 days	Mon 10/2/06	Wed 10/21/09	7,809.87 hrs	\$3,647,068	
7	1.3.2.1	RF Cavities	395 days	Mon 10/1/07	Fri 4/3/09	3,809.87 hrs	\$2,112,368	
8	1.3.2.1.1	Engineering Design & Inspection	395 days	Mon 10/1/07	Fri 4/3/09	2,617.87 hrs	\$319,448	
9	1.3.2.1.1.1	RF Cavity Analysis and Design	110 days	Mon 10/1/07	Fri 2/29/08	592 hrs	\$67,680	
10	1.3.2.1.1.1.1	Complete Final Cavity Conceptual Design	8 wks	Mon 10/1/07	Fri 11/23/07	128 hrs	\$21,120	
11	1.3.2.1.1.1.2	Complete Final Cavity RF and Structural Analysis	4 wks	Mon 11/26/07	Fri 12/21/07	64 hrs	\$10,560	
12	1.3.2.1.1.1.3	Generate Detailed 3D Model of Cavity Body	4 wks	Mon 12/24/07	Fri 1/18/08	160 hrs	\$14,400	
13	1.3.2.1.1.1.4	Complete Detail and Assembly Drawings for Cavity Fab	6 wks	Mon 1/21/08	Fri 2/29/08	240 hrs	\$21,600	
14	1.3.2.1.1.2	Tuner Mechanism Analysis and Design	45 days	Mon 2/18/08	Fri 4/18/08	224 hrs	\$24,960	
15	1.3.2.1.1.2.1	Complete Final Cavity Shell Stiffness Analysis	1 wk	Mon 2/18/08	Fri 2/22/08	16 hrs	\$2,640	
16	1.3.2.1.1.2.2	Complete Final Tuner Conceptual Design & Analysis	3 wks	Mon 2/25/08	Fri 3/14/08	48 hrs	\$9,920	
17	1.3.2.1.1.2.3	Complete Detailed Drawings for Tuner Fab	3 wks	Mon 3/24/08	Fri 4/11/08	120 hrs	\$10,800	2
18	1.3.2.1.1.2.4	Specify Procurement of Tuner Components	1 wk	Mon 4/14/08	Fri 4/18/08	40 hrs	\$3,600	
19	1.3.2.1.1.3	Cavity Window Analysis and Design	20 days	Mon 12/24/07	Fri 1/18/08	64 hrs	\$10,560	
20	1.3.2.1.1.3.1	Complete Window Geometry Conceptual Design	2 wks	Mon 12/24/07	Fri 1/4/08	32 hrs	\$5,280	
21	1.3.2.1.1.3.2	Specify Procurement of RF Windows	2 wks	Mon 1/7/08	Fri 1/18/08	32 hrs	\$5,280	
22	1.3.2.1.1.4	RF Couplers Analysis and Design	45 days	Mon 1/21/08	Fri 3/21/08	184 hrs	\$21,360	
23	1.3.2.1.1.4.1	Complete Final RF Coupler Conceptual Design	2 wks	Mon 1/21/08	Fri 2/1/08	32 hrs	\$5,280	
24	1.3.2.1.1.4.2	Complete RF Coupler Design Details	2 wks	Mon 2/4/08	Fri 2/15/08	32 hrs	\$5,280	
25	1.3.2.1.1.4.3	Complete Detailed Drawings for RF Coupler Fab	3 wks	Mon 3/3/08	Fri 3/21/08	120 hrs	\$10,800	1
26	1.3.2.1.1.5	Module Vacuum System Analysis and Design	35 days	Mon 3/17/08	Fri 5/2/08	144 hrs	\$17,760	
27	1.3.2.1.1.5.1	Develop Final Vacuum System Layout	2 wks	Mon 3/17/08	Fri 3/28/08	32 hrs	\$5,280	
28	1.3.2.1.1.5.2	Perform Final Vacuum System Analysis	1 wk	Mon 3/31/08	Fri 4/4/08	16 hrs	\$2,640	
29	1.3.2.1.1.5.3	Specify Vacuum Components	1 wk	Mon 4/7/08	Fri 4/11/08	16 hrs	\$2,640	
30	1.3.2.1.1.5.4	Complete Detailed Drawings for Vacuum System Components	2 wks	Mon 4/21/08	Fri 5/2/08	80 hrs	\$7,200	1
31	1.3.2.1.1.6	Module Vacuum Shell Analysis and Design	35 days	Mon 4/14/08	Fri 5/30/08	256 hrs	\$30,240	
32	1.3.2.1.1.6.1	Develop Final Vacuum Shell & Support Conceptual Design	2 wks	Mon 4/14/08	Fri 4/25/08	32 hrs	\$5,280	
33	1.3.2.1.1.6.2	Perform Vacuum Shell and Support Stress Analysis	4 wks	Mon 4/28/08	Fri 5/23/08	64 hrs	\$10,560	
34	1.3.2.1.1.6.3	Complete Detailed Drawings for Vacuum Shell & Support	4 wks	Mon 5/5/08	Fri 5/30/08	160 hrs	\$14,400	3
35	1.3.2.1.1.7	Fabrication, Assembly and Testing Follow On and Coordination	355 days	Mon 11/26/07	Fri 4/3/09	1,153.87 hrs	\$146,888	

Ready

EXT CAPS NUM SCRL OVR

start Microsoft Power... Inbox for DLI@b... Microsoft Project... 5:44 AM