

MICE RFCC Module Status

NFMCC-MCTF Collaboration Meeting
LBL, Berkeley, CA

January 25, 2009

Derun Li


Lawrence Berkeley National Lab

Overview

- Engineering design of the RFCC module has been under way at LBNL since early last year
- Preliminary and final design reviews were conducted last year
- Coupling coil design (MICE/MuCool) and fabrication are being provided by ICST of HIT, Harbin, China
- MICE cavity design is heavily based on the successful MuCool 201-MHz prototype RF cavity
 - Fabrication techniques and post processing
 - Engineering design of the RF cavity is complete
 - Cavity fabrication contract to be placed soon (copper sheets arrived Berkeley last week)
- Significant progress on RFCC module engineering design
 - Complete CAD model of the cavity, tuners, support and vacuum
 - Interfaces, shipping, assembly and installation



RFCC Module




Progress Summary

- RFCC PDR and FDR completed during MICE CM21 and CM22
- 201 MHz cavity detailed design and analysis are complete
- Coupling coil design review completed December 2008
- Qualification of three cavity fab vendors completed late last year
- RFP for cavity fab released by LBNL (responses due 1/30)
- Copper cavity material arrived LBNL last week
- Cavity tuner RF & structural analyses and CAD model are complete
- Structural analyses of cavity suspension system is complete
- RF coupler based on design previously developed for MuCool cavity
- Coupling coil interface agreed upon with ICST (working on a few details)
- Cavity cooling water feed-through concept has been developed
- Conceptual design and CAD model of module vacuum vessel, vacuum system and support structure are complete
- Shipping, assembly and installation concepts have been developed



Eight 201-MHz cavities & two CC magnets



MICE RFCC Module Status - NFMCC-MCTF Collaboration Meeting, LBNL, Berkeley

Derun Li - Lawrence Berkeley National Laboratory - January 25, 2009

Page 5




MICE RF Cavity Summary

- Design based on the successful US MuCool prototype
- A slight reduction in cavity diameter to raise the frequency that has been specified and analyzed
- The fabrication techniques used to produce the prototype will be used to fabricate the MICE RF cavities
- Final cavity design was reviewed at CM22 at RAL
- Copper cavity material arrived LBNL last week
- An RFP for cavity fabrication has been released, and a contract is expected to be placed next month
- The first 5 cavities to be delivered by end of CY2009





MICE RF Cavity Design

- 3-D CST MWS parameterized RF model including ports and curved Be windows to simulate frequency, E_{peak} , power loss & etc.
- Estimated frequency variations between cavities should be within ± 100 kHz (after fabrication)
- Absolute frequency: 201.25-MHz \pm 400-KHz
- Approach
 - Slightly modify prototype cavity diameter
 - Target a higher cavity frequency
 - Tune cavities close to design frequency by deformation of cavity body (if needed)
 - Tuners operate in the push-in mode only \rightarrow lower frequency



201 MHz Cavity Concept




Spinning of half shells using thin copper sheets and e-beam welding to join the shells; extruding of four ports; each cavity has two pre-curved beryllium windows, but also accommodates different windows



Cavity Fabrication Drawings

- Detailed fabrication drawings are complete
- All steps of cavity fabrication process are detailed
- Drawings provided to vendors for bidding process



Cavity Fabrication Process Traveler

Cavity Traveler.xls [Compatibility Mode] - Microsoft Excel

	A	B	C	D	E	F	G	H	I	J	K	L	M
1	Cavity Number												
2	1	Part Name	Part Name	Part Name	Part Name	Part Name	Part Name	Part Name	Part Name	Part Name	Part Name	Part Name	Part Name
3		Cavity Half Shell 1	Cavity Half Shell 1	Cavity Half Shell 2	Cavity Half Shell 2	Stiffener Ring	Stiffener Ring	Window Clamp Ring	Window Clamp Ring	Nose Ring Piece	Nose Ring Piece	Cavity Half Shell 1	Cavity Half Shell 2
4	Date	1-Aug	1-Aug	1-Aug	2-Aug	2-Aug	2-Aug		2-Aug	5-Aug	2-Aug		
5													
6	Process Step	Spinning	Full Inspection Physical and RF	Spinning	Full Inspection Physical and RF	Turning	Full Inspection	Turning	Full Inspection	Turning	Full Inspection	e-beam Welding of stiffener ring	e-beam Welding of stiffener ring
7	Process Location	ACME /?	LBNL	ACME /?	LBNL	Mississippi	LBNL	Mississippi	LBNL	Mississippi	LBNL	Roark/Meyer/?	Roark/Meyer/?
8	Status	In process		In process									
9													
10													
11	Cavity Number												
12	2	Part Name	Part Name	Part Name	Part Name	Part Name	Part Name	Part Name	Part Name	Part Name	Part Name	Part Name	Part Name
13		Cavity Half Shell 1	Cavity Half Shell 1	Cavity Half Shell 2	Cavity Half Shell 2	Stiffener Ring	Stiffener Ring	Window Clamp Ring	Window Clamp Ring	Nose Ring Piece	Nose Ring Piece	Cavity Half Shell 1	Cavity Half Shell 2
14	Date	1-Aug	1-Aug	1-Aug	2-Aug	2-Aug	2-Aug		2-Aug	5-Aug	2-Aug		
15													
16	Process Step	Spinning	Full Inspection Physical and RF	Spinning	Full Inspection Physical and RF	Turning	Full Inspection	Turning	Full Inspection	Turning	Full Inspection	e-beam Welding of stiffener ring	e-beam Welding of stiffener ring
17	Process Location	ACME /?	LBNL	ACME /?	LBNL	Mississippi	LBNL	Mississippi	LBNL	Mississippi	LBNL	Roark/Meyer/?	Roark/Meyer/?
18	Status	In process		In process									
19													
20													
21	Cavity Number												
22	3	Part Name	Part Name	Part Name	Part Name	Part Name	Part Name	Part Name	Part Name	Part Name	Part Name	Part Name	Part Name
23		Cavity Half Shell 1	Cavity Half Shell 1	Cavity Half Shell 2	Cavity Half Shell 2	Stiffener Ring	Stiffener Ring	Window Clamp Ring	Window Clamp Ring	Nose Ring Piece	Nose Ring Piece	Cavity Half Shell 1	Cavity Half Shell 2



Cavity Vendor Qualification

- A series of vendor qualification visits were conducted

- Applied Fusion - San Leandro, CA
 - e-beam welding, machining
- Meyer Tool & Mfg., Inc. - Chicago, IL
 - machining
- Roark Welding & Engineering - Indianapolis, IN
 - e-beam welding, machining
- Sciaky, Inc. - Chicago, IL
 - e-beam welding
- ACME Metal Spinning - Minneapolis, MN
 - cavity shell spinning
- Midwest Metal Spinning, Inc. - Bedford, IN
 - cavity shell spinning

Primary vendors



Overall RFCC Module Design

Dynamic Cavity
Frequency Tuners


Mechanical Joining
of the Coupling Coil
and the Vacuum Vessel

Hexapod Strut
Cavity Suspension

RF Coupler

Vacuum System

RF Cavity
Water Cooling



Progress: Other Module Components

- Design and analysis of the cavity frequency tuners is complete, drawings to be done soon
- A hexapod cavity suspension system has been incorporated in the design
- The RF coupler will be based on the SNS design using the off the shelf Toshiba RF window
- The vacuum system includes an annular feature coupling the inside and the outside of the cavity
- Vacuum vessel accommodates interface w/coupling coil
- Beryllium window design is complete; windows are in the process of being ordered (8 per module needed)



Cavity Tuner Components - Section View

Tuner actuator


Pivot pin

Dual bellows
vacuum sealing

Ceramic contact
wear plate between
actuator ball end
and tuner arm




Ball contact only

Fixed (bolted)
connection



Tuner System Analysis


- Model of overall cavity tuning displacements
- Maximum distortion of 0.05 mm (0.002") in the stiffener ring




- One tuner FEA of 1/6 cavity segment
- Maximum cavity stress is 100 MPa
- Cavity will not yield when compressed to full tuning range



Hexapod Strut Mounting to Vessel




Cavity Suspension Analysis




Stress Analysis

- Peak cavity stress due to gravity is the 20-30 MPa (~10% of yield)



Deflection Analysis

- Total mass of cavity assembly is ~410 kg
- Peak deflection: 115 μm




Modal Analysis


- First mode frequency: 43 Hz



Prototype Cavity RF Couplers




- Coupling loops are fabricated using standard copper co-ax
- Parts to be joined by e-beam welding (where possible) and torch brazing
- Coupling loop has integrated cooling
- The RF coupler will be based on the SNS design using the off the shelf Toshiba RF window




MICE Cavity RF Couplers

- A bellows connection between the coupler and the vacuum vessel provides compliance for mating with the cavity



MICE Cavity RF Couplers



Off the shelf
flange “V” clamp
secures RF coupler
to cavity



Progress: SC Coupling Coil Magnets

- Collaboration between LBNL and ICST of HIT, Harbin
- Final design review was held in Harbin (Dec. 2008)
 - Vendor pre-qualification visits
 - Vendor bids for hardware fabrication
 - Contracts should be awarded in Feb. 2009
 - ICST responsible for coil winding
- Test coils
 - Two test coils (small and large) were made at ICST/HIT
 - Test setup is nearly complete and will be tested at end of Feb. 2009
- Details of the CC interface and RFCC module



MICE Coupling Coil Magnets

Thermal shields and intercepts

Cryocoolers


Cold mass supports

Power leads

He condenser


Vacuum vessel

He cooling pipes




Vacuum Vessel Fabrication

- Vacuum vessel material must be non-magnetic and strong therefore 304 stainless steel will be used
- The vacuum vessel will be fabricated by rolling stainless steel sheets into cylinders
- Two identical vessel halves will be fabricated with all ports and feedthroughs



Vacuum Vessel and Coupling Coil



MICE RFCC Module Status - NFMCC-MCTF Collaboration Meeting, LBNL, Berkeley

Derun Li - Lawrence Berkeley National Laboratory - January 25, 2009

Page 24



Schedule Overview

- RFCC design and fabrication project originally expected to be a 3-year project (10/06 to 10/09)
- Coupling coil effort began in 2006 at ICST (Harbin)
- Design and fabrication of other RFCC module components was scheduled to begin 10/07
- Start was delayed due to lack of availability of qualified manpower
- Earlier last year, mechanical engineer A. DeMello joined MICE to work on RFCC module design (FTE)
- Some additional (part-time) manpower now available



