



MuCool Program Overview

Muon Cooling R&D
Alan Bross

- **MuCool Overview** **AB**
 - ◆ Collaboration
 - ◆ MuCool Test Area
 - ◆ Program Synopsis
 - ◆ MuCool Phase II

- 201 MHz RF Program **D. Li**
- 805 MHz RF Program **D. Huang**
- LiH Absorber Program **AB**
- Coupling Coil **M. Green**
- MTA Beam Line (MCTF) **C. Johnstone**

- **Mission**

- ◆ Design, prototype and test all cooling channel **components**
 - ◆ 201 MHz RF Cavities, LH₂ absorbers, SC solenoids
- ◆ Support MICE (cooling demonstration experiment)
- ◆ Perform high beam-power engineering test of cooling section components

- **Consists of 10 institutions from the US, UK and Japan**

RF Development

ANL
Cockcroft Institute
Fermilab
IIT
JLAB
LBNL
Mississippi

Solenoids

LBNL
Mississippi

Absorber R&D

Fermilab
IIT
KEK
NIU
Mississippi
Osaka

MuCool Test Area

- Facility

test of



MTA Hall






RF Cavity R and D




ANL/FNAL/IIT/LBNL/UMiss

- Study the limits on Accelerating Gradient in NCRF cavities in magnetic field
- It has been proposed that the behavior of RF systems in general can be accurately described (predicted) by universal curves
 - ◆ Electric Tensile Stresses are important in RF Breakdown events
- This applies to all accelerating structures




Detailed Modeling Code Now Available


Detailed modeling of breakdown is underway at Tech-X.




field emitted electrons



make a copper plasma




⇒ radiation & heat .



Must define experiments to vet this code

Preliminary results.



NCRF Model Extended to SCRF

- We have extended this model to SCRF and high frequency problems.
- We are working with the Argonne Materials Science Division to develop:
 - ◆ A materials science program to understand chemical, morphology and electronic properties of rf SCRF and NC materials
 - ◆ Cavity tests to determine optimum procedures and performance.
- This program is underway and, using Argonne internal funding, and has produced important results:
 - ◆ We have developed a model of High Field Q-Slope based on magnetic oxides, that seems to explain SCRF cavity data.
 - ◆ We have developed a new procedure to produce niobium surfaces without complex oxides.
 - ◆ We are beginning a program of cavity testing with JLab.
- Using Atomic Layer Deposition and other newly developed materials science techniques we can synthesize and analyze surfaces with unprecedented precision.
 - ▲ Limits maximum gradient


Extension To SCRF

- We are extending our experimental program to explore the ultimate gradient limits of “perfect” surfaces, which have the properties that (ATOMIC LAYER DEPOSITION):
 - ◆ They are smooth at the nanometer level, so local fields ($\sim 1/r$) cannot be high enough to produce field emission or breakdown events
 - ◆ They are layered, with thin superconducting layers that are expected to be resistant to B field quenches.
 - ◆ They are homogeneous, so local “hot spots” should not exist.
 - ◆ They can be applied “in-situ” so they are not subject to assembly defects.
 - ◆ They allow almost complete freedom to choose substrate for conductivity, rigidity, etc. to avoid thermal, Lorentz and microphonics effects.
- We expect we should be able to address known failure modes and produce structures that reach significantly higher gradients in both normal and superconducting systems.

The Basic Problem - B Field Effect

805 MHz Studies


Safe Operating Gradient Limit vs Magnetic Field Level at Window for the three different Coil modes



Gradient in MV/m

Peak Magnetic Field in T at the Window


- Data seem to follow universal curve
 - Max stable gradient degrades quickly with B field
- Remeasured
 - Same results



805 MHz Imaging


Polaroid Pictures of Field emitters

- Inserting polaroids near the window,




- Gives a picture of how the field emitters change with rf field.

8.8 - 17.6 MV/m





Next 805 MHz study - Buttons

- Button test
 - ◆ Evaluate various materials and coatings
 - ◆ Quick Change over




RF R&D - 201 MHz Cavity Design


- **The 201 MHz Cavity - 19 MV/m Gradient Achieved** (Design - 16MV/m)
 - ◆ In low (few hundred G) B field. Still no breakdown. Limited by available power




201 MHz Cavity Operation in B Field



- Initial 201 MHz operation in B Field
 - ◆ Limited to few hundred Gauss
 - ▲ Using Fringe Field of 4T magnet (in blue)



201 in Position



- We have now moved 201 as close as possible to 5T solenoid
- Can obtain $\approx 1.5T$ on near window of 201



LiH Absorber R&D

Production of LiH Disks

- Only 1 vendor was found that would cast LiH
 - ◆ After some reflection (and some input from Chemists from Argonne Lab), the vendor decided casting LiH was too dangerous (production of H₂ gas)
- Working with Y12 (Oakridge)
 - ◆ Found the engineer in charge of their LiH work and he suggested that they press (Hot 150C, Isostatic (30,000 psi) a "loaf" and machine parts to our specification from the loaf
 - ▲ They have achieved 98% theoretical density using this technique
 - ▲ They are doing R&D on casting LiH for their internal programs, but do not recommend it for our application.
 - It is very tricky due to the high temperature (700C +) and the large (30%) shrinkage on cooling
- We are in the process of setting up a contract with them to make a disk for temperature studies and 1 or 2 disks for MICE
 - ◆ Note: The Li in their LiH is ⁶Li
 - ▲ For the mass we will receive, our parts will be considered Nuclear Material
 - This will require additional procedures/paperwork for shipment, but Y12 personnel see no inherent problem




MuCool Phase II

Cryo-Infrastructure Installation/Commission
Beam Line Installation/Commission

MTA Cryo-Infrastructure

- **MTA Reconfiguration**
 - ◆ Commission Cryo-Plant (June 2008)
 - ◆ Install Transfer Line system
 - ◆ Raise Equipment to beam height
 - ◆ New shield wall
- **Working on Project Plan**
 - ◆ ≈ 3 month effort with adequate technician resources
 - ▲ Need 5 technicians full time (estimate is about 2000 hours)
 - ▲ Plus 5 weeks of a welder
 - ▲ Plus \$50k in M&S (Does not include rerouting of RF power)
- **Need to complete before the 2009 (March) Accelerator Shutdown**

Existing Dewar-Fed Cryogen System




- All of this is removed
- New (simpler) shield wall
 - ◆ Will allow for easier pit access to hall
 - ◆ More shielding needed for beam operations in MTA Hall

MTA - Refrigerator Room



Transfer Line System



Transfer Line System




Valve Box
Piping




Completed Valve Box

MTA Beam Line as Installed



MTA Beam Line Group

MuCool Test Area (MTA) Project Organization Chart



First Beam Experiments




- Currently 5T magnet and 201 cavity on floor (below beam ht.)
- We will raise equipment to beam height
 - ◆ Also flip orientation of 201 MHz cavity and magnet
- Goal
 - ◆ First Beam Experiment (Muon's Inc HP RF Test Cell) by end of 2008

MTA Beam Commissioning

- Beam Line commissioning to first beam stop (Linac side of shield wall) may start as early as June
- Still doing radiation shielding assessments
 - ◆ Rerouting RF Power required
 - ▲ Final configuration for this still being developed
- Will start at low intensity
 - ◆ Need Shielding upgrade (over-burden) for high-intensity



Phase II - Configuration



MuCool Plans for the Coming Year

- 805 MHz RF studies – Buttons (with and without B field)
 - ▲ Materials tests
 - ▲ Surface treatment (HP Wash + EP (from UK), ALD (Argonne))
 - ▲ E X B study
- 201 MHz RF
 - ◆ Continue B field studies
 - ◆ Working with Linac Group to improve operational efficiency
- Begin thermal and mechanical tests on HIP LiH absorber prototypes
- Complete MTA cryo infrastructure installation and commission system
- Commission Beam Line
- First tests with Beam Complete by January 09 (MCTF)
 - ◆ Test of Muons Inc. HP H₂ RF test cell with beam