



ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY



201-MHz RF Studies and Plans

Derun Li

Center for Beam Physics
Lawrence Berkeley National Laboratory

MUTAC Review at LBNL
April 8-10, 2008



ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

Outline



- **Introduction**
 - brief review
- **Progress on 201-MHz test program**
 - **RF tests with curved thin Be windows**
 - Curved Be windows installed
 - Cavity retuned to 200-MHz
 - Tested up to 19 MV/m
 - **RF tests with stray magnetic fields of Lab-G magnet**
 - Move the cavity next to Lab-G magnet
 - New transmission line
 - New Vacuum pump
 - Preliminary test results
 - **Simulation study of RF cavity in strong magnetic field**
- **Plans**
 - **More 201-MHz test with SC coupling coil (M. Green's talk)**
 - **Beam test at MTA (A. Boss's talk)**
 - **201-MHz cavities for MICE**
 - Review and plans
- **Summary**



ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

Primary Goals



- Development of **normal conducting 201-MHz cavity** that can operate at a gradient of **~ 16 MV/m** in a **few Tesla magnetic fields environment**
 - Prototype: exploring engineering solutions (challenges)
 - RF conditioning and operation without and with B fields
- **Last MUTAC review**
 - The 201-MHz cavity reached 16 MV/m without external magnetic field
 - The cavity kept at 16 MV/m with \sim a few hundred Gauss stray magnetic fields from Lab-G magnet
- We understand: operating a NC RF cavity (with thin and curved Be windows) at ~ 16 MV/m in strong B field could be very challenging, but to be confirmed experimentally
 - Test with stronger magnetic fields: move the cavity as close as possible to Lab-G magnet
 - SC coupling coil for MUCOOL: being fabricated at ICST, Harbin



ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

201-MHz Prototype Cavity



- The cavity design parameters
 - Frequency: 201.25 MHz
 - $\beta = 0.87$
 - Shunt impedance (VT^2/P): ~ 22 M Ω /m
 - Quality factor (Q_0): $\sim 53,500$
 - Be window radius and thickness: 21-cm and 0.38-mm
- Nominal parameters for cooling channels in a muon collider or a neutrino factory
 - ~ 16 MV/m peak accelerating field
 - Peak input RF power ~ 4.6 MW per cavity (85% of Q_0 , 3τ filling time)
 - Average power dissipation per cavity ~ 8.4 kW
 - Average power dissipation per Be window ~ 100 watts



The 201-MHz cavity at MTA




ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

Test Setup at MTA



The 805-MHz and 201-MHz cavities at MTA, FNAL for RF breakdown studies with external magnetic fields.




805 MHz pillbox cavity

201 MHz cavity




ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

Installation of Curved Be Windows



Be window installation



Cavity surface inspection

RF Tests of Be Windows

- **The cavity reached to ~ 19 MV/m quickly**
 - Cavity frequency had to be retuned
 - Cavity frequency was **stable** during the operation, however, we did observe frequency shift due to RF heating on the windows
 - Frequency shift of ~ 125 kHz (from 0 to ~ 19 MV/m, 150-micro-second pulse, 10-Hz repetition rate) in ~ 10 minutes, well within the tuning range (~ 110 kHz/mm, \pm 4-mm range)
- **With low external magnetic field**
 - Cavity can be operated at ~ 19 MV/m with a few hundred Gauss stray field from Lab-G magnet
- **Tests with stronger external magnetic fields**
 - **SC coupling coil for MuCool**




ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

New Vacuum Pumping System




Getter pumping system:

- 1500 l/s Getter pump
- Backed by a 20 l/s Ion pump
- Rough down by a with a Turbo-pump and dry pump
- Vacuum valves & Ion gages
- System has been running over a month without needing a re-charge
- Has achieved base vacuum level of 2.5×10^{-8} Torr



Vacuum flexible line connection to the Getter pump



Roughing and Ion pump stand


Tests with Magnetic Fields

Lab-G magnet

The 100-cm long coaxial section was replaced by 20-cm one


Separation of the nearest curved Be window from the face of Lab-G magnet is 10-cm (before was 110-cm)

Maximum magnetic field near the Be window ~ 1.5 Tesla (5 Tesla in magnet)



The 201-MHz cavity


Preliminary Test at B=0






ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

Radiation at 0.5-T Field



Preliminary Test Results

- Multi-pactoring was observed at the entire magnetic field range up to 3.75-T (~ 1.1 -T at nearest Be window)
- A strong correlation exists between cavity vacuum and radiation levels
- We have achieved ~ 14 MV/m at 2.5-T (~ 0.75 -T to the nearest curved thin Be window)
- The test results are very encouraging, data analysis is being conducted
- We may need to commission (condition) the 201-MHz cavity longer to reduce the multi-pactoring before we can properly measure and study the magnetic field effects in the stray field
- Numerical studies with external magnetic fields and SC coupling coil






ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY


Numerical Study with B Field




- Preliminary studies, in collaboration with Dr. Zenghai Li at SLAC using Omega-3P and Track-3P codes
 - Cavity with flat windows: 5 MV/m on axis; 2-T uniform external magnetic field; scan of a few points from one cavity side



E field contour



**Trajectories without
external B field**



**Trajectories with
external B = 2-T field**



ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

201-MHz Cavity for MICE




- **Eight 201-MHz cavities + with materials for two more spare cavities**
- **Baseline design: 201-MHz for MUCOOL, but**
 - **Cavity body profile needs to be modified**
 - Resonant frequency
 - Better estimation of spring back after spinning
 - **Port extruding**
 - Port interface is different from the MUCOOL cavity
 - **RF coupler and ceramic window**
 - The same window as for the MUCOOL cavity: Toshiba ceramic windows for SNS
 - **Curved Beryllium windows**
 - Improved design to better control silver alloy flow during the brazing
 - **Tuners and interface with RFCC module**
 - **Post-processing: water cooling pipes, cleaning (EP & water rinsing), low power measurement, tuning, assembly and shipping**



ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

MICE Cooling Channel



Eight 201-MHz RF cavities

LH₂ absorbers

MICE Cooling Channel
Courtesy of S. Q. Yang, Oxford Univ.



ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

Cavity Design Parameters





- **The cavity design parameters**
 - Frequency: 201.25 MHz
 - $\beta = 0.87$
 - Shunt impedance (VT^2/P): $\sim 22 \text{ M}\Omega/\text{m}$
 - Quality factor (Q_0): $\sim 53,500$
 - Be window radius and thickness: 21-cm and 0.38-mm
- **Nominal parameters for cooling channels in a muon collider or a neutrino factory and MICE**
 - $\sim 16 \text{ MV/m}$ ($\sim 8 \text{ MV/m}$) peak accelerating field
 - Peak input RF power $\sim 4.6 \text{ MW}$ ($\sim 1 \text{ MW}$) per cavity (85% of Q_0 , 3τ filling)
 - Average power dissipation per cavity $\sim 8.4 \text{ kW}$ ($\sim 1 \text{ kW}$ at 1 Hz repetition rate and 1 ms pulse length)
 - Average power dissipation per Be window
 $\sim 100 \text{ watts}$ ($\sim 12 \text{ watts}$)



ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

MUCOOL Cavity Review



- Design and engineering at LBNL
- Half shells spun at Acme in Minnesota
- Parts made in Univ. of Mississippi and LBNL
- E-beam welding & port-pulling, cleaning and EP at J-Lab, NASA
- Coupler tests at SNS, Oak Ridge National Lab
- Final assembly and high power tests at MTA, FNAL (March-2006) and reached 16-MV/m without external magnetic field



ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

Cavity Body



- **The frequency for MuCool cavity is slightly lower than 200-MHz, but within the bandwidth of RF source**
 - Mechanical (fixed) tuners available and tested in air
- **MICE cavities**
 - Target frequency is 201.250-MHz
 - One RF source (tube) powers more than one cavity
 - Each cavity will be made (spinning) to frequency very close to 201-MHz
 - Modifying the existing mold used for MUCOOL cavity
 - A new mold (could be new materials)
 - 3D simulations to predict the frequency shifts by ports, curved Be windows and thermal contraction (LN operation)
 - Conceptual tuner designs (fine tuning)




ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

Ports Extruding and Coupler



Development of the technique




Cavity ports being extruded (pulled)



Extruded port



Power coupler and RF window







ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

Curved Be Windows



- We have made two windows so far
 - 21-cm and 0.38-mm thick
 - **Good** braze (between annular frames and foil)
 - Achieved ~ 95 % of the designed profile
 - Thin Ti-N coatings
- The windows have been tested






ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

Tuners for MICE Cavities




Four 201-MHz cavities in each RFCC module; one tuner assembly (six sets of tuners) on each cavity.



- Clocking of tuner position between adjacent cavities avoids interference
- Actuators offset from cavity center plane due to width of coupling coil
- Soft connection only (bellows) between tuner/actuators and vacuum vessel shell

Tuner Concept for MICE Cavity (Sectional View)







ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

Post-Processing



- **Cavity cleaning, assembly and integration**
- **Low power measurements and shipping**



Microsoft Project - WBS-1.3.2-10-08-07(w_MC)

Type a question for help

Tasks Resources Track Report

146,147,148,40,32

WBS Plan has been developed

First four cavities ready in 2010

WBS	Task Name	Work	Original Fixed Cost [\$]	Predecessor
1	MICE	797.5 days	\$3,647,068	
2	MICE Integration	1 day	\$0	
3	Muon Beam Line & Infrastructure	1 day	\$0	
4	MICE Cooling Modules	797.5 days	\$3,647,068	
5	Absorber and Focus Coil Module	1 day	\$0	
6	Cavity and Coupling Coil Module	797.5 days	\$3,647,068	
7	RF Cavities	395 days	\$2,112,368	
8	Engineering Design & Inspection	395 days	\$319,448	
9	RF Cavity Analysis and Design	110 days	\$67,680	
10	Complete Final Cavity Conceptual Design	8 wks	\$21,120	
11	Complete Final Cavity RF and Structural Analysis	4 wks	\$10,560	
12	Generate Detailed 3D Model of Cavity Body	4 wks	\$14,400	
13	Complete Detail and Assembly Drawings for Cavity Fab	6 wks	\$21,600	
14	Tuner Mechanism Analysis and Design	45 days	\$24,960	
15	Complete Final Cavity Shell Stiffness Analysis	1 wk	\$2,640	
16	Complete Final Tuner Conceptual Design & Analysis	3 wks	\$9,920	
17	Complete Detailed Drawings for Tuner Fab	3 wks	\$10,800	2
18	Specify Procurement of Tuner Components	1 wk	\$3,600	
19	Cavity Window Analysis and Design	20 days	\$10,560	
20	Complete Window Geometry Conceptual Design	2 wks	\$5,280	
21	Specify Procurement of RF Windows	2 wks	\$5,280	
22	RF Couplers Analysis and Design	45 days	\$21,360	
23	Complete Final RF Coupler Conceptual Design	2 wks	\$5,280	
24	Complete RF Coupler Design Details	2 wks	\$5,280	
25	Complete Detailed Drawings for RF Coupler Fab	3 wks	\$10,800	1
26	Module Vacuum System Analysis and Design	35 days	\$17,760	
27	Develop Final Vacuum System Layout	2 wks	\$5,280	
28	Perform Final Vacuum System Analysis	1 wk	\$2,640	
29	Specify Vacuum Components	1 wk	\$2,640	
30	Complete Detailed Drawings for Vacuum System Components	2 wks	\$7,200	1
31	Module Vacuum Shell Analysis and Design	35 days	\$30,240	
32	Develop Final Vacuum Shell & Support Conceptual Design	2 wks	\$5,280	
33	Perform Vacuum Shell and Support Stress Analysis	4 wks	\$10,560	
34	Complete Detailed Drawings for Vacuum Shell & Support	4 wks	\$14,400	3
35	Fabrication, Assembly and Testing Follow On and Coordination	355 days	\$146,888	

Ready

start Microsoft Power... Inbox for DLI@b... Microsoft Project... 5:44 AM



ERNEST ORLANDO LAWRENCE
BERKELEY NATIONAL LABORATORY

Summary



- **Curved Be windows were installed and tested**
 - Reached ~ 19 MV/m with stray magnetic fields of a few hundred Gauss
 - Reached to ~ 14 MV/m with ~ 0.75-T (@ nearest Be window) magnetic field by moving next to Lab-G magnet
 - Preliminary results are encouraging
- **Numerical studies of the cavity in magnetic fields started in collaboration with SLAC**
- **Plans for building eight 201-MHz cavities for MICE are developed**
 - Four cavities will be delivered by 2010
- **Need MuCool coupling coil to provide the needed strong magnetic field for further studies**