

# RIA Target Station Design and Infrastructure

**Presented by: Reg Ronningen (MSU)**

**Prepared by Tony Gabriel and Dave  
Conner (Oak Ridge National Laboratory)**

RIA R&D Participants:

Argonne National Lab: J. Nolen

Lawrence Berkley Nation Lab: L. Heilbronn

Lawrence Livermore National Lab: L. Ahle, J. Boles, S. Reyes, W. Stein

Los Alamos National Laboratory: Dave Viera

Michigan State University: I. Baek, G. Bollen, M. Hausmann, D. Lawton, P. Mantica, D. Morrissey, R. Ronningen, B. Sherrill, A. Zeller

Oak Ridge National Lab: J. Beene, T. Burgess, D. Conner, T. Gabriel, I. Remec, M. Wendel

# RIA Overview

- **R&D Activities**
- **Overall Layout and Parameters**
- **Remote Maintenance Requirements**
- **ISOL Target Design and Analysis**
- **Fragmentation Beam Dump Design**
- **Project Status**

# **Rare Isotope Accelerator (RIA)**

## **DOE Sponsored R&D Areas**

- **Beam Simulation**
- **Front End**
- **Driver Linac  
(2<sup>nd</sup> Stripper Region RH Considerations)**
- **Isotope-Separator-on-Line (ISOL)**
- **Fragment Separation- for Fragment Separators**
- **Fragment Separation- for Gas Cell**
- **Post Acceleration**
- **Multi User Considerations**

# ISOL Target

- **Analysis and evaluation of target concepts (Mercury, Tungsten/Water Cooled)**
- **Identification of required utilities and corresponding remote maintenance capabilities**
- **Activation and Heating Calculations**
- **Target Gallery layout and optimization for maximum availability**


# Fragmentation Target

- **Development of simulation codes for heavy ion transport**
- **Evaluation of Beam Dump for full range of production scenarios  
[Cu (water or gas cooled), Lithium Stream]**
- **Development of high-power target concepts**
- **Simulation of radiation doses to magnets and other components**
- **Development of concepts for remote maintenance for damaged components**
- **Materials Research**


# Multi-User Considerations

- **Incorporate capability for simultaneous independent experiments**
- **Multiple target vs. Cost Optimization**
- **Maximize availability**

# The RIA facility schematic layout and areas of R&D



# A Possible RIA Site Layout







## RIA Parameters List

| WBS Parameter                               | BaseValue            | Unit           | Comments |
|---|----------------------|----------------|----------|
| <b>1.0 GLOBAL PARAMETERS</b>                |                      |                |          |
| 1. 0. Maximum beam power on target          | 400                  | kw             |          |
| 1. 0. Primary beam kinetic energy on target | 1.0                  | GeV protons    |          |
| 1. 0. Beam Frequency                        | 400                  | MeV/u uranium  |          |
| 1. 0. Protons/sec                           | Steady State         |                |          |
| 1. 0. Ion Types                             | 2.5x10 <sup>15</sup> |                |          |
| 1. 0. Front end length                      | H thru Uranium       |                |          |
| 1. 0. Linac Length                          | TBD                  |                |          |
| 1. 0. HEBT Length                           | TBD                  |                |          |
| 1. 0. RTBT Length                           | TBD                  |                |          |
| 1. 0. Maximum uncontrolled beam loss        | 1                    | W/m            |          |
| 1. 0. ISOL Target material                  | Hg,W,Ta,Ucx          | .....          |          |
| 1. 0. Fragmentation target material         | Li, Graphite, ??     |                |          |
| 1. 0. Number of ISOL targets                | 2                    | (3rd optional) |          |
| 1. 0. Number of Fragmentation targets       | 2                    |                |          |
| 1. 0. Number of stripper stations           | 2                    |                |          |
| 1. 0. Initial number of instruments         | ??                   |                |          |

# RIA Target Gallery Layout





# RIA Beam production area




**Challenges:**  
High power + high power density  
Frequent target changes

- **High-power target design** (ANL, ORNL, MSU)
- **Development of overall concepts for the beam production areas** (MSU, ORNL, LLNL, LBNL, LANL, ANL)



**ISSUES**

**CELL ACCESS  
(CONTAMINATION)  
SHIELD DOORS**



100 TON  
HIGHBAY CRANE

50 TON GALLERY  
CRANE

FRAG  
MAINTENANCE/DECON  
CELL

FRAG SHIELDED  
STORAGE AREA

**HIGH BAY AREA**

DUAL  
SERVOMANIPULATORS  
(SHOWN IN STORAGE  
POSITION)

TRANSFER CELL  
(HANDS ON  
MAINT.)

INCELL SHIELD  
DOORS

BASEMENT/  
WASTE DISPOSAL

ISOL TARGET  
STATIONS


FRAGMENTATION  
TARGET STATIONS


# SHIELDED HOTCELL



ISSUES      MODULE SIZE  
DOSE LIMITS?

# BRIDGE MOUNTED SERVO MANIPULATOR





ISOL BEAMS

FRAGMENTATION  
BEAMS

**OAK RIDGE NATIONAL LABORATORY**  
**U. S. DEPARTMENT OF ENERGY**







ISSUES


COMPONENT SIZE


LIFETIME


COUPLINGS














ISSUES  
MODULE SIZE  
HEATING  
SEALS







# ISOL TARGET UTILITIES









# RIA TARGET BUILDING

RIA Overview

# Requirements for RIA Target Building Remote Maintenance

- **Large Hot Cell Remote Handling Equipment**
- **Large Hot Cell Configuration and Function**
- **Component Design for Remote Handling**
- **Remote Tooling**

# Remote Handling Manipulators

- **There are three basic types of manipulators:**
  - **Wall Mounted Master-Slave Manipulator**
  - **Power-arm mounted on bridge**
  - **Servomanipulator mounted on bridge**

# Master-Slave Manipulator (MSM)

- **Advantages**
  - Highly dexterous
  - Force reflecting
  - Inexpensive
  - Reliable (HD models)
  - Work well with a shielding window
- **Disadvantages:**
  - Limited reach
  - Small effective working volume
  - Require a shielding window workstation
  - Can be overloaded by operator




# Bridge Mounted Servomanipulator

- **Advantages:**

- Highly dexterous handling
- Force reflecting
- 5 to 8 X hands-on task times
- Reduces need and cost of special remote handling features on components
- Moderately powerful
- Can be equipped with an auxiliary hoist to assist with material handling

- **Disadvantages:**

- Expensive
- Complex and potentially unreliable
- Mechanically compliant arm limits positioning accuracy in robotic mode



# Hot Cell Video Cameras - Rad Tolerant

Radiation hard IST/REES  
R981 Cameras (industry  
standard )

- Advantages


- Wall and bridge mountable
- Can include lights and cameras
- Rad resistance to  $>10^5$  rads
- Reliable

- Disadvantages

- High cost
- Hands-on maintenance required
- Black and White only
- Relatively poor visual quality
- Limits hot cell background



SNS Proposal for Wall Mounted Hot Cell Cameras





# Hot Cell Functions


- **Hot cells have two primary functions**
  1. **Radiation Control; passive elements such as concrete, shielding windows and vault doors.**
  2. **Contamination Control; active systems**
    - high efficiency ventilation
    - low level liquid waste water treatment
    - Solid waste treatment, handling and shipping
- **Each of the three active systems is expensive and large**

# Hot Cell Material Handling

- **Gravity is our only friend; therefore.....**
- **Virtually all material handling is accomplished by bridge cranes; as a result:**
  - **Cells tend to be high to provide head room, hook height and clearance over servomanipulator bridges.**
  - **Cells tend to be long and narrow to reduce the bridge width and allow for easier monitoring of bridge motions.**
  - **Working areas of cell determined by bridge coverage; thus crowning of the cell is advantageous.**
  - **Cell modules should be designed for the minimum possible load since larger cranes have less coverage.**

# Crane and Servomanipulator Combinations

- Overhead bridge crane is mounted above the servo bridge
- Servomanipulator and transporter with Aux hoist must be able to pass bridge crane to operate on both sides of the hook
- Retrieving tools and lift fixtures is difficult and time consuming
- RIA will probably require multiple cranes and servo systems to provide backup and reduce turn-around times.




# Personnel Access vs. Fully Remote

- **A Fully Remote Hot Cell Is Completely Different from a Personnel Accessible Cell in Cell Design, Component Design, Layout, Tooling, and Operation.**
- **A Cell Designed To Operate Partially Hands-on Cannot Be Easily Converted To Full RH.**
- **Cooling water vaults can be entered after 1-3 days of radiation cool-down if filters and IX columns have local shielding.**

# Remote Maintenance Design

- **Process components modularized based on expected maintenance frequency**
- **Remote handling interfaces incorporated to facilitate remote disassembly and assembly of modules with standardized remote tooling and lift fixtures**
- **Maintenance accomplished by replacement of failed component**



SNS Hg Pump

# Identification of Tasks

Remote handling tasks must be identified early; the list is the basis of design for the RH system and the components

Summary Top Level Maintenance Design Parameters

|    |                                    | Expected | Oper. Life | Restoration | Time Goals | Spare | Repair |
|----|------------------------------------|----------|------------|-------------|------------|-------|--------|
| 1. | 0. Target Process Components       |          |            |             |            |       |        |
|    | 1. Target Module                   | >4       | Mo         | < 5         | D          | Yes   | No     |
|    | 2. Primary Mercury Pump            | ~20      | Yr         | <30         | D          | No    | No     |
|    | 3. Primary Mercury Pump Motor      | ~5       | Yr         | < 5         | D          | Yes   | No     |
|    | 3. Process Control Sensors         | 1        | Yr         | <2          | D          | Yes   | No     |
|    | 4. Vacuum Pump Module              | ~5       | Yr         | <5          | D          | No    | No     |
|    | 6. Mercury Process Gas Valves      | ~5       | Yr         | <5          | D          | Yes   | No     |
|    | 7. Mercury Transfer Valve          | ~20      | Yr         | <5          | D          | No    | No     |
|    | Mercury Transfer Valve Operator    | ~5       | Yr         | <2          | D          | Yes   | No     |
|    | 8. Hg/Water Heat Exch.             | >15      | Yr         | <60         | D          | No    | No     |
|    | 9. Pipe Spools (Frequent Coupling) | >10      | Yr         | <60         | D          | No    | No     |
|    | 10. Collection Basin               | LOF      |            |             |            | No    | No     |


# Remote lift fixture examples



# Two-step fission targets for $\geq 100$ kW beam power

## Principle of 2-step fission targets:

- Neutron converter for neutron production and dissipation of beam power
- Surrounding blanket of fissionable material for rare isotope production



## Original proposal (J. Nolen, ANL):

**Li-cooled W converter**

## Are there alternatives to Li + W ?



(MSU, ORNL, LLNL)

- 1) **Mercury as target and coolant**
- 2) **Water-cooled W**

## Choice of converter type has impact on design of target area →

- Investigation of neutron/fission yields, beam and decay heating, radiation damage for 400 kW 2-step target
- Conceptual design studies of cooling schemes







# Axial flow Design

## Water velocity of 18.2 m/s


|                     | Grid 1            | Grid 2            |
|---------------------|-------------------|-------------------|
| W Volume            | 80%               | 80%               |
| Velocity            | 18.2 m/s          | 18.2 m/s          |
| Inlet Temperature   | 40°C              | 40°C              |
| Outlet Temperature  | 62°C              | 62°C              |
| Pressure Drop       | 97 psi            | 100 psi           |
| Max W Temperature   | 224°C             | 214°C             |
| Max D2O Temperature | 143°C<br>75/210°C | 134°C<br>76/191°C |




# two wheels and one stationary beam dump



# Example of a RIA Pre-Separator





**Optics design**  
**Power Densities**  
**Radiation Fields**




AIR  
INLET/OUTLET  
JUMPERS

TARGET  
MODULE


VACUUM  
ENCLOSURE



# floor between dump motor and vacuum space



# Beam dump section; magnet vacuum space extended to top of above floor.





# RIA Project Status

- **CD0 granted**
- **Unfunded Mandate—Construction start  
Sept 2008**