

The Fermilab Roadmap, Project X, and Muon Facilities


Steve Holmes

NFMCC Meeting
March 17, 2008

Sketch of Integrated Plan (Y2K, Sept. 2007) f

LHC including Upgrades, Particle Astrophysics (including Dark Matter and Dark Energy)

ILC R&D, EDR, Engineering, Decision, Industrialization, Construction, Running




Project X Facility Overview

f

Project X is a high intensity proton facility aimed at supporting a world leading program in neutrinos and rare decays.

NO_νA initially,
DUSEL later?



Project X Facility Overview

Scope

f

- The R&D program supports a facility scope that includes:
 - A new 8 GeV, superconducting, H^- linac;
 - A new beamline for transport of 8 GeV H^- from the linac to the Recycler Ring;
 - Modifications to the Recycler required for 8 GeV H^- injection, accumulation, and delivery of protons to the Main Injector;
 - Modifications to existing beamlines to support transfer of 8 GeV protons from the Recycler to the Main Injector;
 - Modifications to the Main Injector to support acceleration and extraction of high intensity proton beams over the range 60-120 GeV;
 - Modifications to the NuMI facility to support operations at 2 MW beam power;
 - Modifications to the Recycler to support a new extraction system that will allow delivery of 8 GeV protons in support of a dedicated flavor program.
-

Project X Overview

High Level Performance Goals

Linac

Particle Type	H ⁻	
Beam Kinetic Energy	8.0	GeV
Particles per pulse	5.6×10^{13}	
Pulse rate	5	Hz
Beam Power	360	kW

Recycler

Particle Type	protons	
Beam Kinetic Energy	8.0	GeV
Cycle time	1.4	sec
Particles per cycle to MI	1.7×10^{14}	
Particles per cycle to 8 GeV program	2.2×10^{14}	
Beam Power to 8 GeV program	206	kW

Main Injector

Beam Kinetic Energy (maximum)	120	GeV
Cycle time	1.4	sec
Particles per cycle	1.7×10^{14}	
Beam Power at 120 GeV	2300	kW

f



		NAME		DATE		SCALE		FERMI NATIONAL ACCELERATOR LABORATORY	
		DESIGNED				1' = 500'-0"		LIFE OF THE FUTURE (CONCEPTUAL) DESIGN SUBMITTAL	
		CHECKED							
		APPROVED						LINAC PROTON DRIVER	
		SUBMITTED						SITE PLAN	
REV.	DATE	DESIGNED BY		DRAWN BY		DRAWING NO.		CD-0	
						4-2-1		1	
								REV.	

Project X R&D Goals

Program Goals

- The goal of the Project X R&D program is to provide support for a Critical Decision 1 (CD-1) in 2010, leading to a CD-2/3a in 2011.
 - Design and technical component development;
 - Fully developed baseline scope, cost estimate, and schedule for CD-2
 - Formation of a multi-institutional collaboration capable of executing both the R&D plan and the follow-on construction project.
- The primary technical goal is a complete facility design that meets the needs of the US research program, as established via CD-0.
 - 2 MW of beam power over the range 60 – 120 GeV,
 - simultaneous with at least 100 kW of beam power at 8 GeV,
 - Compatibility with future upgrades to >2 MW at 8 GeV.

Project X R&D Goals

Technical Goals

- Complete preliminary design and cost estimate for Project X:
 - technical and conventional construction elements,
 - systems integration, and
 - installation and commissioning plan.
- A supporting technology development program targeting key accelerator physics and engineering challenges
- Alignment with the ILC and SRF programs:
 - Development of shared technologies to the benefit of both efforts
 - Cavity/cryomodule design, rf sources, e-cloud, civil infrastructure
 - Project X linac designed to accommodate accelerating gradients in the range 23.6 – 31.5 MV/m (XFEL – ILC)
 - Final design gradient determined prior to CD-2.
- Preliminary identification of performance upgrade paths

Project X R&D Goals

Management/Organization Goals

- Formation of a multi-institutional collaboration to carry out the Project X R&D program and to prepare a plan for construction.
- Development all project documentation and organizational structures required by DOE 413.3.
- Timeline:
 - 2008: CD-0
 - Form Project X R&D Collaboration
 - 2009:
 - Start project documentation (including CDR), and accompanying R&D program
 - 2010: CD-1
 - Finish CDR, form collaboration to undertake construction project
 - 2011: CD-2/3a
 - Establish project baseline (scope, cost, schedule)

Project X R&D Strategy

Preliminaries

f

- Proton Driver Design Studies over 2002-2004
 - Director's Review in March 2005
 - Project X Preliminary Report - August 1, 2007
 - Delivered to Fermilab Directorate Long Range Steering committee
 - Reviewed by Fermilab Accelerator Advisory Committee
 - “We congratulate the Project X team on an innovative design...Project-X is especially suitable for Fermilab in the current scenario of a not well-defined schedule of ILC construction, because of synergies with ILC...The committee therefore very strongly supports the work that is planned for Project-X.”

<http://projectx.fnal.gov/AACReview/ProjectXAacReport.pdf>
 - Project X Accelerator Physics and Technology Workshop - Nov. 12-13, 2007
 - 175 attendees from 28 different institutions.

<http://projectx.fnal.gov/Workshop/ProjectXWorkshopReport.pdf>
-

56 Cryomodules

7 Cryomodules

6 Cavity-6 quads / Cryomodule

7 Cryomodules (8 cav., 4 quads)

37 ILC-like Cryomodules

The diagram illustrates the LCLS-II injector layout, showing two cryomodule sections. The top section consists of 8 cavities with 4 quadrupoles per cryomodule, followed by 7 cavities with 2 quadrupoles per cryomodule. The bottom section consists of 8 cavities with 1 quadrupole per cryomodule. Each cavity is represented by a light blue box with a red dot above it, and each quadrupole is represented by a blue box with a red dot above it. The layout is symmetrical and shows the arrangement of the injector components.

Project X R&D Strategy

Major System Requirements

f

Req. No.	Description	Req.	Unit	Reference Requirements			
1.0	General						
1.1	120 GeV Beam Power	2.3	MW				
1.2	8 GeV Beam Power	360	kW				
1.3	8 GeV Slow Spill Beam Power	200	kW				
1.4	8 GeV Slow Spill Duty Factor	55	%				
1.5	120 GeV Availability	75	%				
1.6	8 GeV Availability	80	%				

Req. No.	Description	Req.	Unit	Reference Requirements			
2.0	325 MHz Linac						
2.1	Average Beam Current	9	mA	1.2			
2.2	Pulse Length	1	mS	1.2			
2.3	Repetition rate	5	Hz	1.2			
2.4	325 MHz Availability	98	%	1.6			
2.5	Peak RF Current	14.4	mA	2.1	2.11	2.13	2.14
2.6	Final Energy	420	MeV	3.6			
2.7	Energy Variation (rms)	1	%	3.10			
2.8	Bunch Phase jitter (rms)	1	degree	3.11			
2.9	Linac Species	H-		4.1			
2.10	Transverse Emittance (95% normalized)	2.5	π -mm-mrad	5.7	5.8		
2.11	Macro Bunch Duty Factor	67	%	5.10	5.12		
2.12	Macro Bunch Frequency	53	MHz	5.12			
2.13	Micro Pulse Length	10.4	μ S	5.13			
2.14	Micro Pulse Period	11.1	μ S	5.13			

Project X R&D Strategy

Major System Requirements

Req. No.	Description	Req.	Unit	Reference Requirements			
3.0	1300 MHz Linac						
3.1	Average Gradient (ILC portion)	26	MV/meter				
3.2	Average Gradient (S-ILC portion)	23	MV/meter				
3.3	Average Beam Current	9	mA	1.2			
3.4	Pulse Length	1	mS	1.2			
3.5	Repetition rate	5	Hz	1.2			
3.6	1300 MHz Availability	88	%	1.6			
3.7	Initial Energy	420	MeV	2.6			
3.8	Length (approx.)	700	meters	3.1	3.13		
3.9	Peak RF Current	14.4	mA	3.3	3.15	3.17	3.18
3.10	Linac Species	H-		4.1			
3.11	Energy Variation (rms)	1	%	4.9			
3.12	Bunch Phase jitter (rms)	1	degree	4.9			
3.13	Final Energy	8	GeV	4.10			
3.14	Transverse Emittance (95% normalized)	2.5	π -mm-mrad	5.7	5.8		
3.15	Macro Bunch Duty Factor	67	%	5.10	5.12		
3.16	Macro Bunch Frequency	53	MHz	5.12			
3.17	Micro Pulse Length	10.4	μ S	5.13			
3.18	Micro Pulse Period	11.1	μ S	5.13			

Project X R&D Strategy

Major System Requirements

Req. No.	Description	Req.	Unit	Reference Requirements			
4.0	8 GeV Transfer Line						
4.1	Injection Stripping efficiency	98	%				
4.2	Length (approx.)	1000	meters				
4.3	Maximum average activation level	20	mrem/hr				
4.4	Availability	98	%	1.6			
4.5	Momentum Aperture	+/- 0.8	%	3.10			
4.6	Minimum Transverse Aperture	25	π -mm-mrad	3.13	4.3		
4.7	Maximum Dipole Field	0.05	T	4.1	4.3		
4.8	Transfer Efficiency	99.99	%	4.3			
4.9	Final Energy Variation	+/- 0.11	%	5.10			
4.10	Energy	8	GeV	5.1			

Req. No.	Description	Req.	Unit	Reference Requirements			
5.0	Recycler						
5.1	Energy	8	GeV				
5.2	Storage Efficiency	99.5	%				
5.3	Average Recycler Beam Current	0.6	A	1.2			
5.4	Availability	95	%	1.6			
5.5	Injection Rate	5	Hz	2.3			
5.6	Maximum Space Charge Tune Shift	0.05		5.2			
5.7	95% normalized transverse emittance	25	π -mm-mrad	5.6			
5.8	r.m.s. normalized transverse emittance	13	π -mm-mrad	5.6			
5.9	Bunching factor	2		5.6			
5.10	Longitudinal emittance per Bunch	0.5	eV-Sec	5.6	5.12		
5.11	Cycle Time	1.4	S	6.1			
5.12	RF Frequency	53	MHz	6.2			
5.13	Abort Gap Length	700	nS	6.3			
5.14	Peak Recycler Beam Current	2.4	A	6.5			

Project X R&D Strategy

Major System Requirements

f

Req. No.	Description	Req.	Unit	Reference Requirements
6.0	Main Injector			
6.1	120 GeV cycle Time	1.4	S	
6.2	RF Frequency	53	MHz	
6.3	Abort Gap Length	700	nS	
6.4	Acceleration Efficiency	99	%	
6.5	Main Injector Beam Current	2.4	A	1.1
6.6	Final Energy	120	GeV	1.1
6.7	120 GeV Beam Power	2.3	MW	1.1
6.8	Availability	87	%	1.5
6.9	Injection Energy	8	GeV	5.1
6.10	Longitudinal emittance per Bunch	0.5	eV-Sec	6.2 6.11
6.11	Space Charge Tune Shift	0.05		6.4
6.12	95% normalized transverse emittance	25	π -mm-mrad	6.11
6.13	r.m.s. normalized transverse emittance	13	π -mm-mrad	6.11
6.14	Bunching factor	2		6.11
7.0	8 GeV Slow Spill			
7.1	8 GeV Slow Spill Beam Power	200	kW	1.3
7.2	Peak Spill Rate	280	$\times 10^{12}$ pps	1.3 1.4 7.5
7.3	8 GeV Slow Spill Duty Factor	55	%	1.4
7.4	8 GeV Availability	80	%	1.6
7.5	Cycle Time	1.4	S	6.1
7.6	Peak Recycler Beam Current for slow spill	0.8	A	7.2
8.0	120 GeV Targeting			
8.1	120 GeV Beam Power	2.3	MW	1.1
8.2	120 GeV Availability	95	%	1.5
8.3	Cycle Time	1.4	S	6.1


Project X R&D Plan

Master Schedule

- Based on resource loaded schedule (RLS – see report for readable version)
- Covers FY2008-2011
- Incremental to ILC, SRF, HINS

Major Milestones

CD-0 Approved	8/1/08
Start CD-1 Documentation	9/1/08
Complete CD-1 Document.	4/1/10
Start CD-2 Documentation	5/3/10
CD-1 DOE Review	6/1/10
CD-1 Approved	8/2/10
Complete CD-2 Document.	4/1/11
Start CD-3 Documentation	5/2/11
CD-2 DOE Review	6/1/11
CD-2/3a Approved	9/1/11



Project X R&D Plan

Budget Profile


Project X R&D Plan Budget Profile							
(Dollar amounts in millions, fully burdened)							
		FY08	FY09	FY10	FY11	FY12	TOTAL
SWF		\$6.7	\$10.5	\$19.1	\$26.3		\$62.6
M&S		\$1.5	\$4.9	\$6.2	\$13.7		\$26.3
TOTAL		\$8.1	\$15.5	\$25.4	\$40.0		\$88.9
		↑		↑	PED	↑	
		CD-0		CD-1		CD-2/3a	

Project X R&D budget profile


- Scientists not included
- Can produce this table with any combination of scientists in or out, FY08 or AY\$, burdened or unburdened
- Incremental to ILC, SRF, and HINS programs

Project X R&D Plan


An Integrated SRF Plan




Evolution of a world-leading neutrino program: Present




Evolution of a world-leading neutrino program



Evolution of a world-leading neutrino program



Evolution of a world-leading neutrino program



Evolution of a world-leading neutrino program

Project X beam to DUSEL:

- enhancing the sensitivity markedly


Project X
Beam Power (kW)

DUSEL (WC or/and LAr)
(>2 MW, 50 – 120 GeV)


(ν Detector = Proton Decay Detector)

Recycler
Main Injector


Project X Linac



Evolution of a world-leading neutrino program **f**




Evolutionary Path to $\mu^+\mu^-$ Collider



Consistent Vision as Presented to P5^f by R. Palmer

A Phased Approach



18

Summary

f

- Design concept exists for a facility capable of delivering in excess of 2 MW beam power over the energy range 60 – 120 GeV, simultaneous with 8 GeV beam power in the range 100 – 200 kW.
 - Major sub-system performance goals established
 - Potential upgrade paths to multi-MW at 8 GeV exist
 - Design aligned with needs of ILC development
- R&D plan developed covering the period through CD2/3a (2011)
 - Integrates effort on Project X, ILC, and HINS
 - Resource plan exists
- Working towards organizing as a national project with international participation.
- Retain good communication with the NFMCC/MCTF to assure Project X is designed to preserve utility in a future muon facility.