

# MuCool Overview

Muon Cooling R&D  
Alan Bross

# Outline

- **MuCool Overview** **AB**
  - ◆ Collaboration
  - ◆ MuCool Test Area
  - ◆ Program Synopsis
  
- **MTA RF Program** **Derun Li**
  - ◆ 805 MHz program
    - ◆ Pillbox cavity
    - ◆ Button cell
    - ◆ High Pressure Gas filled Test Cell (Muons Inc.)
  - ◆ 201 MHz program

# MuCool

- **Mission**

- ◆ Design, prototype and test all cooling channel **components**
  - ◆ 201 MHz RF Cavities, LH<sub>2</sub> absorbers, SC solenoids
- ◆ Support MICE (cooling demonstration experiment)
- ◆ Perform high beam-power engineering test of cooling section components

- Consists of 10 institutions from the US, UK and Japan

## RF Development

ANL  
Cockcroft Institute  
Fermilab  
IIT  
JLAB  
LBNL  
Mississippi

## Solenoids

LBNL  
Mississippi

## Absorber R&D

Fermilab  
IIT  
KEK  
NIU  
Mississippi  
Osaka

# MuCool Test Area

- Fac  
ion

test of




# MTA Hall




# MTA

- The MTA is the focus of our Activities
  - ◆ RF testing (805 and 201 MHz)
  - ◆ High pressure H<sub>2</sub> gas-filled RF
  - ◆ LH<sub>2</sub> Absorber tests
  - ◆ High Intensity Proton Beam
    - Will start with low intensity



# MTA Hall Instrumentation



# RF Cavity R and D

ANL/FNAL/IIT/LBNL/UMiss



# RF R&D Program

- **Basic Questions:**

- ◆ Can we do anything to make MICE work better?
- ◆ How does magnetic field affect rf cavities"
- ◆ What materials and material properties are desirable?
- ◆ What surface modification is possible?
- ◆ NF and Muon Colliders also require SCRF, Can we optimize this?

- **Accomplishments**

- ◆ Better understanding of conditioning with magnetic field in 805 cavity.
- ◆ Full gradient operation of 201 MHz cavity in solenoid fringe field
- ◆ Installation of Be windows and button test assembly.
- ◆ Better modeling of breakdown limits.
- ◆ Involvement with SCRF and material science community


# RF R&D Program II

- Major papers:

- ◆ X ray Spectra, Nucl. Instrum. Meth. Phys. Rev. A. 472, 600 (2001)
  - <http://www-mucool.fnal.gov/mcnotes/public/pdf/muc0139/muc0139.pdf>
  - Measurements of x-rays from a single cell cavity
- ◆ Open Cell Cavity, Phys. Rev. STAB 6, 072001 (2003)
  - <http://link.aps.org/doi/10.1103/PhysRevSTAB.6.072001>
  - Measurements of 6 cell cavity, dark current measurements, w/wo B fields, comp. with other cavities, tensile stress
- ◆ Cluster emission, Phys. Rev. STAB 7, 122001 (2004)
  - <http://link.aps.org/doi/10.1103/PhysRevSTAB.7.122001>
  - Emission of clusters, thermal and field dependence,
- ◆ Breakdown mechanics, Nucl. Instrum. and Meth A 537, 510, (2005)
  - <http://www-mucool.fnal.gov/mcnotes/public/pdf/muc0286/muc0286.pdf>
  - General theory of tensile stress triggered breakdown
- ◆ Magnetic fields, Phys. Rev. STAB 8, 072001 (2005)
  - <http://link.aps.org/doi/10.1103/PhysRevSTAB.8.072001>
  - Measurements with 805 MHz pillbox, measurement of  $s^2(b)$
- ◆ Surface damage, Phys. Rev. STAB 9, 062001 (2006)
  - <http://link.aps.org/doi/10.1103/PhysRevSTAB.9.062001>
  - Relationship between surface damage and maximum operating fields.


# Fundamental Focus Of RF R&D

- Study the limits on Accelerating Gradient in NCRF cavities in magnetic field
- We believe that the behavior of RF systems in general can be accurately described (predicted) by universal curves
- This applies to all accelerating structures




# 805 MHz

Safe Operating Gradient Limit vs Magnetic Field Level at Window for the three different Coil modes




- Data seem to follow universal curve
  - Max stable gradient degrades quickly with B field
- Remeasured
  - Same results
  - Does not condition



# RF R&D - 201 MHz Cavity Design

- The 201 MHz Cavity - *16 MV/m Gradient Achieved*
  - ◆ New data on x-ray backgrounds will be presented



# Absorber R and D

IIT/KEK/NIU/Osaka/UMiss

# Absorber Design Issues

- 2D Transverse Cooling

$$\frac{d\epsilon_N}{ds} = -\frac{1}{\beta^2} \frac{dE_\mu}{ds} \frac{\epsilon_N}{E_\mu} + \frac{\beta_\perp (0.014 \text{ GeV})^2}{2\beta^3 E_\mu m_\mu L_R}$$


and

$$\epsilon_{N,\min} = \frac{\beta_\perp (14 \text{ MeV})^2}{2\beta m_\mu \frac{dE_\mu}{ds} L_R}$$

- Figure of merit:  $M = L_R dE_\mu / ds$

$M^2$  (4D cooling) for different absorbers

Material	$\langle dE/ds \rangle_{\min}$ (MeV g <sup>-1</sup> cm <sup>2</sup> )	$L_R$ (g cm <sup>-2</sup> )	Merit
GH <sub>2</sub>	4.103	61.28	1.03
LH <sub>2</sub>	4.034	61.28	1
He	1.937	94.32	0.55
LiH	1.94	86.9	0.47
Li	1.639	82.76	0.30
CH <sub>4</sub>	2.417	46.22	0.20
Be	1.594	65.19	0.18



**H<sub>2</sub> is clearly Best -  
Neglecting Engineering Issues  
Windows, Safety**

# Convective Absorber Activities




- First Round of studies of the KEK absorber performed in the MTA
  - ◆ GHe used to input power



# Convective Absorber Activities II

KEK LH2 absorber test - Evolution of LH2 temperature gradient versus applied power  
(with +/- 5% error)




Temperature gradient (TC-106-H - TC-110-H) versus applied heat for several LH2 absorber bath temperatures.

$$dT=2.4K \text{ at } 20W \rightarrow dT=9K \text{ at } 75W ?$$

$$( T_{\max}=23K, T_{\min}=14K )$$

# Convective Absorber Activities




- KEK Convector Absorber upgrades
  - ◆ Electrical Heater
  - ◆ New Temperature sensors
  - ◆ LH liquid level sensor
- Have now been installed and system has been tested
  - ◆ Ready for LH<sub>2</sub> run
    - After safety approval

Absorber Body being modified in Lab 6 at Fermilab

# LiH Test Program

- Produce encapsulating cast (not pressed) samples
  - ◆ Small disks (5-10 cm)
    - Test casting procedures
    - Examine mechanical properties
    - Destructive tests for voids
  - ◆ Large disk (30 cm) for detailed thermal conductivity studies
    - External Cooling + Internal Heating
    - Potential absorber for MICE Phase I
      - Non-instrumented, no cooling


# Engineering Design for Large Disks




# Thermal Properties Test

## SET UP FOR THE THERMAL TEST

Epoxy all possible exposed LiH seams or coat the whole disc with paralene



Thermocouples



Heater to be attached inside this tube

Removable, flexible silicone cooling tube (3/8"OD, 1/16" wall)

# MTA Cryo-Infrastructure


- We are making good progress with completion of the cryo-plant and transfer-line system.
  - ◆ Transfer line system parts complete
- Our goal is to install/commission the system this FY (*well our goal was to install last FY*)
  - ◆ Before the shutdown (August) in we can start by June
    - We define the beginning of the window to be when the cryo-plant is up and running (producing LHe)
  - ◆ After the shutdown otherwise
- Our current operating costs (LHe) for the MTA magnet are **\$3-5k/week**
  - ◆ Fermilab is providing \$100k of support for MTA operations
    - Will allow us to run the magnet off LHe dewars for the remainder of FY07 if required

# Existing Dewar-Fed Cryogen System



- All of this is removed
- New (simpler) shield wall
  - ◆ Will allow for easier pit access to hall
  - ◆ More shielding needed for beam operations in MTA Hall

# MTA - Refrigerator Room Artist's Conception





# Storage Area



GHe, LN<sub>2</sub>  
Storage  
Heat Exch.


# Compressor Room



# Refrigerator Room



# Transfer Line System




# Transfer Line System

Valve Box  
Piping





Completed  
Valve Box



Refrig  
Room  
Valve  
Can






Xfer  
Line



# MuCool Phase II

Cryo-Infrastructure Installation  
Beam Line Installation


# MTA Beam Line



- 400 MeV beamline for the MTA has been designed
  - ◆ Under Craig Moore/Carol Johnstone
    - External Beams Department
  - ◆ Engineering Design mature
    - Cost
  - ◆ Safety Analysis
    - Linac Area and Beamline
    - Shielding Assessment for MTA
  - ◆ First Phase will be low-intensity
    - Funded by Fermilab + NFMCC
    - Installation group now formed
      - F. Garcia (Proton source group)

# MTA Beam Line Group

MuCool Test Area (MTA) Project  
Organization Chart




# First Beam Experiments





- Currently 5T magnet and 201 cavity on floor (below beam ht.)
- First experiments will pitch beam down to center of magnet
  - ◆ Allows for early tests of gas filled cavity operation in intense beam
  - ◆ Very-low integrated intensity
    - Few full-intensity linac pulses

## Phase II



- Raise equipment to beam height
- Install cryo-infrastructure
  - ◆ Valve box
  - ◆ Transfer lines
  - ◆ Weld system
  - ◆ Connect to cryo-plant
- Expect 2-3 month duration with appropriate technical resources





- Addition of Coupling Coil (B field studies of 201 operation) requires the 201 MHz cavity to be rotated 180 degree

# MuCool Plans for the Coming Year

- 805 MHz RF studies - Buttons (with and without B field)
  - Materials tests
  - Surface treatment
  - Use information from ultra-high resolution surface studies
    - Local Electrode Atom Probe
- 201 MHz RF
  - ◆ Conditioning in B field
  - ◆ Install Curved Be Windows and repeat
- Second round of tests with KEK convective absorber
  - ◆ Window of opportunity is until cryo installation starts
- Begin thermal and mechanical tests on cast LiH absorber prototypes
- Complete MTA cryo infrastructure installation and commission system
- Begin Installation of beam line components during summer shutdown