

A photograph of a particle accelerator tunnel, showing a series of curved, metallic structures that form a path. The structures are arranged in a perspective that leads towards a bright opening at the end of the tunnel. A blue semi-transparent rectangular box is overlaid on the center of the image, containing the title text in yellow and green. The text reads "The International Muon Ionization Cooling Experiment".


# The International Muon Ionization Cooling Experiment






**Aim: to demonstrate the principle of ionization cooling as well as the ability to safely operate a cooling channel.**

# Ionization Cooling - Theory






# Ionization Cooling - MICE




# MICE Final Layout



# Challenges


- Cooling channel is predicted to produce ~ 10% cooling.
- We would like to measure this to ~ 1%.
- Require an emittance measurement resolution of 0.1%
- Timing wrt RF phase from TOF.
- Operate RF cavities in magnetic fields.
- Hydrogen safety (LH<sub>2</sub> in proximity to RF cavities!)

# Aspirational MICE Schedule as of April 2008



**STEP I**


February-July 2008



**STEP II**

UK PHASE I


September 2008



**STEP III/III.1**


November 2008  
to summer 2009

UK PHASE II




**STEP IV**

Delivery of 1st FC  
october 2009!



**STEP V**  
spring 2010



**STEP VI**  
Q4 2010  
-2011

# Organisation

- Spokesmouse – A. Blondel (Geneva)
- Deputy Spokesmouse – M. Zisman (LBNL)

- Executive Board
- Technical Board
- Collaboration Board
- Editorial Board
- Speakers' Bureau
- WBS structure:

Muon Ionisation Cooling Experiment: WBS -- Draft 18Oct07				
MICE	Level 2	Level 3	Level 4	Apsimor/Nichols
	2.0-MICE-Muon-Beam	2.0.1-Upstream beam line	2.0.11-Target 2.0.12-Vacuum-vessels 2.0.13-Vacuum-services 2.0.14-Electrical-services 2.0.15-Water-services 2.0.16-Alignment	Long Long Booth Kearsley Hughes, Shaun Hughes, Martin Govans Loughry
		2.0.2-Downstream-beamline	2.0.21-Q35-refurbishment 2.0.22-Linde-refrigerator 2.0.23-PSI-solenoid 2.0.24-Q4-9-installation 2.0.25-Water-services	Long Spensley Courthold Courthold Spensley Govans
		2.0.3-Beam-monitors	2.0.31-Monitors 2.0.32-Installation-upstream 2.0.33-Installation-downstream	Tilley Sellberg Kearsley Spensley
		2.0.4-XMas2007-shutdown		Hayler
	2.1-MICE-Hall and infrastructure	2.0.2.1-Magnetic-shielding-walls 2.0.2.2-MICE-Hall-floor	2.0.2.2.1-plinth 2.0.2.2.2-false-floor	Hayler Hayler Hayler Hayler
		2.0.2.3-Rolling-platforms 2.0.2.4-Water 2.0.2.5-Air-conditioning 2.0.2.6-Power 2.0.2.7-Liquid-hydrogen-system 2.0.2.8-MLCR 2.0.2.9-Networking 2.0.2.10-Cabling 2.0.2.11-FPS		Govans Govans Griffiths Ivanyushenkijov Kyberd Brandwood Griffiths Alexander
	2.2-MICE-Instrumentation:	2.2.1-TOF 2.2.2-CKov 2.2.3-Spectrometer-solenoid 2.2.4-Tracker	2.2.4.1-Mechanical 2.2.4.2-VLPC-system 2.2.4.3-Electronics 2.2.4.4-DAQ 2.2.4.5-Software 2.2.4.6-Slow-control 2.2.4.7-Trigger-distribution	Bross Brossini Chernaldji Virostek Long Rarher Bross Hart Yoshida Ellis Leaver MacWaters Nichols Chimenti Gradlich MacWaters
	2.3-MICE-Cooling-Channel:	2.2.1-Absorber-focus-coil-module 2.2.2-RF-cavity-coupling-coil-module 2.2.3-Vacuum-system 2.2.4-PF-power	2.2.1.1-Absorber 2.2.1.2-Focus-coil-module	Zisman Lau Ishimodi/Cummings Lau Li Lau (TBC) Moss




# Project Management

- Project Management Team:
  - Project Manager: R. Apsimon
  - Technical Coordinator: A. Nichols
  - Hall Manager: W. Spensley
  - Hall Foreman: A. Jamdagni, P. Flower
  - ISIS Liason: C. Rogers
  - MICE Operations Manager (rotating position)
- Project on good footing, however:
  - R. Apsimon & P. Flower have been granted retirement.




# Technical Coordination

- Big-ticket items committed:
  - South shield wall support structure
  - Air conditioning units
  - Concrete floor removal
- Design work almost complete:
  - False floor
  - North wall shield support structure
  - DSA roofing and walkways
- Remaining design work:
  - MICE hall roof layout
  - Installation drawings for CDM records



# Magnetic Shielding








- Maximised the net benefit to the experiment.
- Can run Step I and complete the construction.

- Design complete for complex south wall.
- North wall design underway.
- Final quote for magnetic steel plates.
- Big impact on other work and operation of experiment.
- Mezzanine closely coupled to walls.
- Part of H<sub>2</sub> system.
- Needs to be built with walls.





# MICE Beam Line





# MICE Beam Line



# Beam Line Status

- Permission obtained to use target in ISIS for three runs over the past week.
- Mechanical installation of decay solenoid complete – not tested yet, problems with the refrigerator
- All quadrupoles and dipoles installed.
- Some power supply and water problems to be fixed on a few quadrupoles.



# Decay Solenoid

- Transfer line is connected and has checked out OK.
- The electrical connections to the solenoid are done and most of the pipe work is done.
- The remaining pipe work does not require access to the DSA and will be complete in the coming weeks.
- Plan to start a cold test on 14<sup>th</sup> April and arrangements are being made for the relevant experts from Linde and PSI to be present to support this test.




# Second Target






- Before we can bring the target that is in ISIS into routine operation, a second target operating elsewhere at RAL is required.
- Second target is due to be complete on 15<sup>th</sup> May.
- Poor QA in the previous manufacturing process has been identified and corrected.
- ISIS are becoming more comfortable with the target operation and so far have consistently increased our budget of “dips” as we approach the previous limit.

# MICE Control Room


- Almost complete.
- DAQ racks filling up, cabling has begun.
- Slow controls, DAQ and target PCs installed and used for data taking.
- PPS racks complete and installed.
- Network in place, further work still required.








# MICE Detectors



# TOF System




- PMT assemblies show an increasing rate of failure under heavy testing.
- 8 tubes returned to Hamamatsu.
- Expected delivery at RAL in early May.



# KL, SW Calorimeters



- Tests and calibrations of the KL are ongoing.
- Trigger counters with magnetic shielding have been built.
- Test and calibration runs of the KL have begun.
- Construction & testing of SW prototype successful.



USA



# CKOV

- Both CKOV detectors have been installed at RAL.
- First pion signals were observed in the past week.





- Track
- Track
- All






# Software

- G4MICE (MICE Simulation, Reconstruction and Analysis software) continues to be developed and is now also used for MANX studies.
- MICE now has a Virtual Organisation on the GRID.
- Tracker Station QA data analysis was performed on the GRID.
- Monte Carlo studies are ongoing.

# TrackerQA Analysis

- Data from 12 Stations (6-17) analysed.
- Total of 12,389,135 events processed.
- 167 of 173 files transferred (6 failures)



# Funding Agencies Committee

- MICE spokesperson and project manager.
- ISIS Director
- Representatives of each funding agency.
- Terms of reference:
  - Receive reports from MICE Project Board and monitor progress of international MICE project.
  - Receive and review reports from each funding nation on contributions to the overall project.
  - Consider cost and schedule issues for the project.
  - Monitor risk and approve contingency.
  - Review and endorse management structure.
  - Prepare the funding and financial aspects of the international project for phase 2.
  - Agree the annual budgets, future profile and schedule.
- Next meeting: 11<sup>th</sup> April



# UK Funding Situation

- STFC funding short fall of £80M announced at the end of 2007.
- Given permission to negotiate the coil contract.
- The target date for letting contract is 11<sup>th</sup> April.
- This is a bit optimistic, but should still be possible in April.
- Consequence is step IV is late compared with the previous schedule.
- UKNF has been asked to present a 3 year plan with budget guidance.
- This is very good news – we can make a plan not just stumble through another financial year.

# ISIS User Runs

- To date we have been operating the target during machine development periods.
- We have demonstrated the ability to run parasitically (the normal mode of operation for MICE).
- Once ISIS/RPA are convinced of the radiation and operational safety, MICE will be able to operate during ISIS user runs.
- It may be necessary for ISIS to cancel one user run. With warning it may be possible for us to mitigate the effect on the schedule.

# Conclusions - Status

- Step I of MICE has started!
- Both dipoles have been powered and particles observed by beam line instrumentation and the CKOV detectors.
- Need to successfully operate the second target, install TOF0 and TOF1 and KL and to complete the false floor and iron shield in order to complete stage 1.



# Conclusions – Planning

- Step two should occur in the September-October run after the spectrometer magnet arrives (August).
- Step three should occur late 2008 or early 2009.
- Focus pair order has been agreed, with first delivery expected in October 2009.
- Coupling coils and RF cavities are consistent with this.