

# MUCOOL RF R&D Activities

John Corlett

Accelerator and Fusion Research Division

LBL

# Cooling RF R&D - Staff



## *Berkeley*

John Corlett

Mike Green

Neal Hartman

Subal Kar

Mike Leung

Derun Li

Bob MacGill

## *Fermilab*

Norbert Holtkamp

Tom Jurgens

Al Moretti

Zubao Qian

Vincent Wu

## *IIT*

Ed Black

## *Mississippi*

Don Summer

Mike Boone

# Cooling RF R&D - Issues




- High accelerating field ( 15 - 30 MVm<sup>-1</sup>)
- Large beam pipe apertures ( 38 - 16 cm diameter)
- Strong magnetic field ( 5 T)
  - Maximize shunt impedance - minimize power requirements
    - Novel accelerating structures
      - Closed-cells
        - » Windows or grids of tubes
- *breakdown, multipacting, heating, dark current, ...*

# Cooling RF R&D

- 805 MHz
  - Collider parameters
  - “End” of cooling section
- Hardware
  - /2 interleaved cavity
    - Be windows
    - Low-power test cavity
      - LN<sub>2</sub> temperature
    - High-power test cavity
  - -mode open cell cavity
    - Cold-test cavity
    - High-power test cavity
  - Superconducting solenoid
  - Lab G development

- 201.25 MHz RF cavity
  - Neutrino factory parameters
  - “Beginning” of cooling section
- Paper studies
  - /2 interleaved cavity
    - Be windows
    - Thin-walled tubes
  - Integration into cooling channel

# 805 MHz $\pi/2$ pillbox with Be windows



- Per-cell dissipated power 250 W
- Be window dissipated power 43 W

–  $E_0 = 30 \text{ MVm}^{-1}$

– 3 filling


– 15 Hz

–  $Q = 21,000$

» kHz cell-to-cell stability


–  $Z_0 = 54 \text{ M } \Omega \text{ m}^{-1}$

–  $ZT^2 = 44 \text{ M } \Omega \text{ m}^{-1}$



# Low-power test cavity

- Test Be windows
  - Mechanical stability
    - »  $\mu\text{m}$  stability
    - RF heating
    - Halogen lamp heating
    - Low temperature
    - » Gain factor 2 in  $ZT^2$





"SW\_CAVITY\_LO-2-dimension"  
 /home/me57/ols/macgill/CORLETT/MUON\_COLLIDER

Macgill


# Low-power Test Cavity Measurements

- Low-temperature tests in vacuum
  - 500 W RF input
  - Halogen lamp heating
  - LN<sub>2</sub> cooling



# RF windows for 805 MHz cavities




- Be foils 0.005” thick
- 99.8% Be
- Foil diffusion bonded to Be frame
  - 0.063” thick rings
  - 6.3” internal diameter
  - 7.58” outside diameter
- Foil flatness 0.001”
- Pre-stressed
  - Different CTE alloys foil/frame
- Windows purchased for tests
  - *Not “designed” in detail*








# Window Measurements Halogen Lamp Heating

- Al and Be foils
  - Al not stressed
  - Heat with halogen lamp
    - Temperature profile broadly similar to RF heating






# Halogen Lamp Heating Room Temperature

- Al and Be foils
- Halogen lamp heating






# Halogen Lamp Heating Low Temperature

- Cool cavity with LN<sub>2</sub>
- Heating with halogen lamp
  - Window does not move
    - $f$  due to cavity body  $T$



# RF Heating Low Temperature





- Heating with RF

- $Q_1$  4000
  - Bolt-together cavity
- RF on for 5 min cycles
- Window does not move
  - $f$  due to cavity body  $T$



» “Null” measurement

# Be Window FEA


- ANSYS model of Be and Al foil windows
- Include pre-stress of Be foil
  - Difficult to model accurately
- Room temperature foil distortion arises from temperature gradient in foil
  - Need increased conductivity
    - thicker foils
    - low temperature
  - Increase pre-stress?



# Increased Be Window Thickness




# High-power Pillbox Cavity



- Test Be foils at high gradient in magnetic field
  - Breakdown
  - Multipacting
  - Temperature stability
    - Test in Lab G facility



# 805 MHz 6-cell $\pi$ -mode Cavity






# 805 MHz 6-cell $\pi$ -mode Cavity


- Al prototype tests
  - Determine final dimensions for Cu cavity
- Cu cavity machining has begun
  - 12 tuning points per cell




# $\Pi$ -Mode Frequency and Q Measurement



# Π-Mode Input Impedance Measurement




# $\Pi$ -Mode Field Measurement



# Superconducting Magnet

- Magnet produces up to 5T field on axis
  - Solenoid or bucking mode
  - models fields in solenoid channel

A Comparison of Measured and Calculated Induction Versus Distance While Operating in the Gradient Mode





# Superconducting magnet



## Status of Lab G

- Modulator and klystron in place
- Water system installed up to cave
- Interlocks being assembled




- Superconducting magnet to be installed
- Shielding roof to be completed
- RF power waveguide to be installed



Parameter	Crossed Tube	Pill Box
Frequency	201.25 MHz	201.25 MHz
Accelerating Phase Angle	Sin(25 degrees)	
Peak Accelerating Field	15.0 MV/m	15 MV/m
Peak Surface Field	22.5 MV/m	15 MV/m
Kilpatrick Limit	14.8 MV/m	14.8 MV/m
Cavity Type	Open Cell with crossed tubes over aperture	Beryllium foil windows over 15 cm radius apertures
Cavity Dimensions	internal r is 0.600 m internal cell length, /3, is 0.432 m.	internal radius is 0.600 m, internal cell length, /3, is 0.432 m. length of accelerating section is 0.864 m.
Impedance	28.4 M /m	34.1 M /m
Shunt Impedance	20.3 M /m	23.3
Transit Time Factor T	0.845	0.827
Peak Voltage per Cell	6.5 MV	5.7 MV
Q	47,500	52,600
Fill Time	38 $\mu$ s, critically coupled	42 $\mu$ s
rf Pulse	114 $\mu$ s	125 $\mu$ s
Peak Power per Cell	3.45 MW	2.8 MW
Average Power per Cell	8.0 kW	5.3 kW
Window Type	4 cm diameter Al crossed tubes	15 cm radius, 127 $\mu$ m thick Be foil
Average Power on Tubes	30 W (worst tube)	53 W (heated from both sides)



# 201.25 MHz RF Layouts



# 201 MHz Gridded (Crossed-tube) Cavity



- Large apertures accommodated
- Air cooling inside tubes
- Coupling between cavities  $\sim 0.1\%$
- Cavities independently excited
- Tube walls can be thin  $< 0.1$  mm
- Spun construction - 1.27cm (0.5 in) wall thickness
- Tunable by wall displacement

# R&D Plans

Item	Description	Completion date	M&S	Labor (m-m)
Be window finite element analysis	Develop FEA model of Be foil window, determine engineering feasibility for 805 MHz and 201 MHz size windows.	Jun-00	\$10,000	1
Thin-walled tube analysis	Develop engineering model for thin-walled tube structures	Jun-00		1
Low-power open-cell test cavity	Complete measurements of low-power open-cell test cavity	Jun-00	\$1,000	1
Install superconducting magnet in Lab G		Jun-00	\$25,000	3
Lab G 805 MHz RF	Complete installation and commissioning of 805 MHz RF system	Jul-00	\$5,000	2
Be window model	Design and build test windows based on FEA results	Sep-00	\$30,000	2
Thin-walled tube test model	Design and build test tube assemblies	Sep-00	\$30,000	2
805 Mhz open-cell high-power cavity	Design and build a prototype high-power open-cell cavity at 805 MHz to test behaviour in high RF fields.	Sep-00	\$100,000	3
805 MHz high-power pillbox with Be end plates	Design and build a high-power pillbox cavity at 805 MHz to test Be surfaces to determine behaviour in high RF and magnetic fields.	Oct-00	\$70,000	3
Testing 805 MHz high-power open cell cavity	Testing high-power open cell cavity at 805 MHz	START 10/1/2000	\$35,000	4
Test Be window(s)	Test window(s)	Nov-00	\$1,000	1
Test thin-walled tube assemblies	Testtube assemblies	Nov-00	\$1,000	1
Testing 805 MHz pillbox high-power cavity with Be end plates	Testing high-power pillbox cavity at 805 MHz to test Be surfaces	START 1/1/2001	\$35,000	4
Modifications and further high-power cavity testing at 805 MHz	Unforeseen challenges, changing geometries, surface coatings, etc...	CONTINUES through Sep-01	\$100,000	8
Total (805 MHz):			\$443,000	36

Item	Description	Completion date	M&S	Labor (m-m)
Preparation for 201 MHz equipment in Lab G.	Purchase and install 201 MHz tetrode and power supplies into Lab G. Coaxial lines, interlocks, etc. Prepare for superconducting solenoid.	Feb-01	\$400,000	12
Prototype high-power 201 MHz cavity	Design and build a prototype high-power cavity at 201 MHz to test behaviour in high RF fields and magnetic fields. Use Lab G facilities with 200 MHz tetrode installed.	May-01	\$360,000	12
201 MHz cavity testing	Testing high-power cavity at 200 MHz. Conditioning, operating at high-power varying pulse length, varying magnetic field...	Oct-01	(costs included in lab G. preparation)	4
Modifications to cavity	Based on experimental experience, modify cavity - e.g. anti-multipactor coatings? Change geometry of power feedthrough? Improve cooling in some areas?	Feb-02	\$120,000	4
201 MHz cavity testing	Additional testing of high-power test cavity	May-02	\$30,000	3
Second high-power RF cavity	Develop second iteration of cavity design based on experience with first prototype and it's modifications. Manufacture second cavity.	Jan-03	\$300,000	7
201 MHz cavity testing	Testing second high-power test cavity	Mar-03	\$30,000	3
Total (201MHz):			\$1,240,000	45

# Summary



- 805 MHz
  - Be windows studies continuing
    - Low power test cavity measurements (  $\pi/2$  interleaved pillbox)
    - ANSYS FEA model
    - Designing high-power test cavity
  - -mode 6-cell open-cell cavity
    - Al model testing complete
    - High-power Cu cavity being built
  - Lab G preparations complete this summer
    - » High power tests in Lab G this year
- 201 MHz
  - Designing high-power test cavity
    - » Build high-power test cavity next year
    - » Develop 201 MHz RF test stand in Lab G